


AD-A123 608


EMBANKMENT CRITERIA AND PERFORMANCE REPORT MISSOURI  
RIVER FORT PECK LAKE MONTANA VOLUME II DRAWINGS(U) ARMY  
ENGINEER DISTRICT OMAHA NEBR SEP 82

1/2

UNCLASSIFIED

F/G 13/13 NL






MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

# EMBANKMENT CRITERIA AND PERFORMANCE REPORT

SEPTEMBER 1982

ADA 123608

## MISSOURI RIVER FORT PECK LAKE, MONTANA



US Army Corps  
of Engineers  
Omaha District

VOLUME II.  
DRAWINGS

DTIC  
JAN 21 1983  
H

88

4

Contains color  
reproduction of  
all DTIC products.  
Will be in black and  
white.

DISTRIBUTION STATEMENT A  
Approved for public release;  
Distribution Unlimited

DTIC  
JAN 21 1983









FIGURE 2

FORT PECK DAM AND RESERVOIR EMBANKMENT CRITERIA AND PERFORMANCE REPORT PLATE 1-1

2

WAR DEPARTMENT





RECEIVED  
INSPECTED

Accession	
RTIS UP	
DTIC TAB	
Unannounced	
Distribution:	
By	
Availability	
Dist	Spec
A	



NOTE:  
THIS DRAWING IS TRACED FROM DRAWING  
NO. D-10-15, DATED MARCH 1958 & REVISED  
D-10-15, AND IS IDENTICAL EXCEPT THAT  
IT HAS BEEN REDUCED TO STANDARD  
DIMENSIONS.


FIGURE 3





VICINITY MAP





APPROXIMATE DATA ON DAM

LENGTH	21,026 FT.
MAX. HEIGHT	230 FT.
MAX. WIDTH AT BASE	4,900 FT.
WIDTH AT TOP	100 FT.
EARTH REQUIRED	122,000,000 CU. YDS.
GRAVEL REQUIRED	4,000,000 CU. YDS.
ROCK REQUIRED	1,000,000 CU. YDS.

APPROXIMATE DATA ON RESERVOIR


CAPACITY	19,412,000 AC. FT.
AREA	245,000 ACRES
LENGTH	100 MILES
SHORE LINE	1,400 MILES
MAX. WIDTH	16 MILES


MISSOURI RIVER IMPROVEMENT  
 NAVIGATION—FLOOD CONTROL—POWER—IRRIGATION  
**FORT PECK DAM**

CONSTRUCTION FEATURES




2






REVISIONS		
DATE	DESCRIPTION	MADE BY CORRECTED BY
12-6-36	Holes Added	CCC RD
June 37	Outline Dam, Dike & Abut	C.V.J.

MISSOURI RIVER IMPROVEMENT			
NAVIGATION - FLOOD CONTROL - POWER - IRRIGATION			
<b>FORT PECK DAM</b>			
<b>INDEX TO CORE HOLES</b>			
11 SHEETS		SCALE: 1" = 100 FT.	SHEET NO.
U. S. ENGINEER OFFICE, GLASSBORO, MONTANA			
DESIGNED BY	APPROVED	APPROVED	
CHECKED BY	REVIEWED	REVIEWED	
DATE	DATE	DATE	DATE
			63-2




LINE 44+00-U



LINE 9+40-U

FORT PECK DAM AND RES





FORT PECK DAM AND RESERVOIR

EMBANKMENT CRITERIA AND PERFORMANCE REPORT

PLATE 3-2

2060

392

383

385

386

2020

1980

1940

1900

1860

LINE 4+50 - U

2060

377

376

375

374

373

372

371

370

369

368

367

366

365

364

363

362

2020



1980

1940

1900

1860


LINE OF OUT-OFF WALL




LEGEND  
BUREAU OF SOIL CLASSIFICATION

2040	SAND	
	GRAVELLY SAND	
2020	LOAM	
	SANDY LOAM	
	GRAVELLY LOAM	
1980	SANDY GRAVELLY LOAM	
	CLAY	
	SANDY CLAY	
1960	CLAY LOAM	
	GRAVELLY CLAY LOAM	
	SANDY CLAY LOAM	
1900	SANDY GRAVELLY CLAY LOAM	
	GRAVEL	
	SANDY GRAVEL	
1860	WEATHERED SHALE	
	SOFT SHALE	
	SUB-FIRM SHALE	
	FIRM SHALE	


MISSOURI RIVER IMPROVEMENT					
FORT PECK DAM					
FOUNDATION					
SOIL PROFILES					
IN SHEETS					
SCALE: 1" = 10'					
SHEET NO. 2					
U.S. ENGINEER OFFICE,					
FORT PECK, MONTANA					
MISSOURI RIVER DIVISION,					
FEB 1935					
Submitted		Recommended		Approved	
Assisted Engineer		Senior Engineer		Chief of Engineers	
Drawn	Traced	Checked	Transmitted	File	
				33112	




LINE 3+50-D



LINE 7+80-D



LINE 3+50-0





LINE 7+80-0

LEGEND  
BUREAU OF SOIL CLASSIFICATION

SAND	
GRAVELLY SAND	
LOAM	
SANDY LOAM	
GRAVELLY LOAM	
SANDY GRAVELLY LOAM	
CLAY	
SANDY CLAY	
CLAY LOAM	
SANDY CLAY LOAM	
GRAVELLY CLAY LOAM	
SANDY GRAVELLY CLAY LOAM	
SANDY GRAVEL	
WEATHERED SHALE	
SOFT SHALE	
SUB-FIRM SHALE	
FIRM SHALE	

MISSOURI RIVER IMPROVEMENT  
FORT PECK DAM  
FOUNDATION  
SOIL PROFILES

10 SHEETS	SCALE 1" = 40'	SHEET NO. 3
U.S. ENGINEER OFFICE, FORT PECK, MONTANA	MISSOURI RIVER DIVISION, FEB 1933	
Submitted	Recommended	Approved
Designed	Checked	Tracked
Drawn	Tracked	Filed
		33-112



LINE 12+00-D

LINE 16+30-D

LEGEND  
BUREAU OF SOIL CLASSIFICATION

SAND	
GRAVELLY SAND	
LOAM	
BANDY LOAM	
GRAVELLY LOAM	
BANDY GRAVELLY LOAM	
CLAY	
CLAY LOAM	
GRAVEL	
BANDY GRAVEL	
WEATHERED SHALE	
SOFT SHALE	
SUB-FIRM SHALE	
FIRM SHALE	

MISSOURI RIVER IMPROVEMENT  
FORT PECK DAM  
FOUNDATION  
SOIL PROFILES


IN SHEETS		SCALE 1"=400'	SHEET NO. 4
U.S. ENGINEER OFFICE, FORT PECK, MONTANA		MISSOURI RIVER DIVISION MARCH 1936	
Submitted	Recommended	Approved	
Associate Engineer	Senior Engineer	Major Corps of Engineers	
Drawn	Traced	Checked	Transmitted
FILE			

FORT PECK DAM AND RESERVOIR


EMBANKMENT CRITERIA AND PERFORMANCE REPORT

PLATE 3-5


2




LINE 20+50-D



LINE 37+50-D








LEGEND


BUREAU OF SOIL CLASSIFICATION

SAND	[Pattern]
GRAVELLY SAND	[Pattern]
LOAM	[Pattern]
SANDY LOAM	[Pattern]
GRAVELLY LOAM	[Pattern]
SANDY GRAVELLY LOAM	[Pattern]
CLAY	[Pattern]
SANDY CLAY	[Pattern]
GRAVELLY CLAY	[Pattern]
CLAY LOAM	[Pattern]
SANDY CLAY LOAM	[Pattern]
GRAVEL	[Pattern]
SANDY GRAVEL	[Pattern]
DISINTEGRATED SHALE	[Pattern]
WEATHERED SHALE	[Pattern]
SOFT SHALE	[Pattern]
SUB-FIRM SHALE	[Pattern]
FIRM SHALE	[Pattern]




MISSOURI RIVER IMPROVEMENT			
FORT PECK DAM			
FOUNDATION			
SOIL PROFILES			
34 SHEETS	SCALE 1"=400'	SHEET NO. 5	
U.S. ENGINEER OFFICE,	100 FT. 1"=400'	MISSOURI RIVER DIVISION,	
FORT PECK, MONTANA		MARCH 1935	
Submitted	Recommended	Approved	
Checked	Traced	Checked	Traced
By	Date	By	Date
			33-11-2

# WAR DEPARTMENT



TYPICAL CROSS SECTION OF DAM


ZONE	ELEVATION	AVERAGE EFFECTIVE SIZE IN MILLIMETERS	AVERAGE CLAY CONTENT PER CENT
1 and 6	Below 2100	>0.1	<3.0
1 and 6	2100-2180	>0.1	<5.0
1 and 6	Above 2180	>0.05	<8.0
2 and 5	Below 2255	>0.005	<10.0
3	Below 2200	<0.005	>10.0 & <30.0
3	Above 2200	<0.01	<30.0
4	Below 2255	Same as Zone 3 or Zone 5	
Sand Plugs	Below 2180	<0.10	<20.0
Above Sand Plugs	2180-2255	<0.01	<30.0




CROSS SECTION OF DAM

REVISED 3-31-38. F.K.M.		REVISED 8-31-38. R.A.W.	
MISSOURI RIVER IMPROVEMENT			
FORT PECK DAM			
SPECIFICATIONS			
IN 2 SHEETS		SHEET NO. 1	
SCALE AS SHOWN			
U.S. ENGINEER OFFICE, FORT PECK, MONT. 2-3-1937			
Submitted:	Approved:	Recommended:	Approved:
<i>[Signature]</i>			
Checked by:	Reviewed by:	Presented with report:	File No.:
C.E.M.	C.E.M.		


Figure 6








FORT PECK DAM




FORT PECK DAM  
EFFECTIVE SIZE OF FILL SAMPLES, STA. 40+00  
GROSS SECTION





FORT PECK DA





FORT PECK DAM  
CLAY CONTENT OF FILL SAMPLES, STA. 40+00  
GROSS SECTION





# PLAN


Scale 1" = 300'

Note: Contours indicate approximate total thickness of clay strata in foundation

## FORT PECK DAM STABILITY ANALYSIS-UPSTREAM

### PLAN OF PROPOSED


Prepared in Office of Division  
Missouri River Division



### PROFILE 940' UPSTREAM FROM AXIS


Scale 1" = 300'

7



**FORT PECK DAM**  
**STABILITY ANALYSIS-UPSTREAM FOUNDATION**

**PLAN OF PROPOSED BERM**  
Prepared in Office of Division Engineer  
Missouri River Division



3



6+00 U

8+00 U

10+00 U

12+00 U

Upstream Berm

(Would raise  $S_r$  to 1.37 T/sq ft and reduce  $C$  to 1.31 T/sq ft)

Gravel

CLAY

Shearing Strength at toe  
 $S_r = 1.14 \text{ T/sq ft}$ 

1.81 T/sq ft (Max required Shearing Strength)

SAND

Rigid boundary  
force:Water and toe computed:  
at 10 ft dam

Validation load = 21.64 T/sq ft

at foot constants:  $\tan \phi = 0.25$ ,  $c = 0.40$ 

form

at constants for ultimate failure

 $c = 0.33$ 

10.12 T/sq ft

0.61 T/sq ft


## FORT PECK DAM

## STABILITY ANALYSIS-UPSTREAM FOUNDATION

JURGENSON'S METHOD

STATION 58+00

Prepared in Office of Division Engineer - Mo. River Div.



#### CONSTANTS ADOPTED FOR ANALYSIS

SHELL Unit Wt. 100 lb/cu ft  $\tan \phi = 0.65$   $c = 0$   
(Saturated to elev. 2040)

CORE Unit Wt. 105 lb/cu ft  $\tan \phi = 0.20$   $c = 0$   
(Saturated to elev. 2200)

CLAY FOUNDATION Unit Wt. 120 lb/cu ft  
(See Note for values of  $\tan \phi$  and  $c$ )

Case I

Case II

Case III

Samples for

CURVE No.	FACTOR OF SAFETY		
	Case I	Case II	Case III
1	1.7	1.9	1.8
2	1.5	1.7	1.7
3	0.9	1.1	1.1

SHELL

400 U

500 U

800 U

1000 U

#### NOTE

Case I:  $\tan \phi = 0.18$ ,  $c = 0.5$  T/sq. ft. - Constants determined by average of quick shear tests using load applied to sample at time of apparent yield point.

Case II:  $\tan \phi = 0.21$ ,  $c = 0.33$  T/sq. ft. - Constants determined by average of quick shear tests using load applied to sample at time of ultimate failure.

Case III:  $\tan \phi = 0.24$ ,  $c = 0.12$  T/sq. ft. - Constants determined by weighted average according to thickness of soil strata, using yield point test data for sampled strata and estimating  $\tan \phi$  and  $c$  for non-sampled strata.

Samples for testing were obtained from holes F-1, F-3, F-10 and F-20.

### FORT PECK DAM

#### STABILITY ANALYSIS - UPSTREAM FOUNDATION


#### CRITICAL SLIDING PLANE

#### SWEDISH METHOD - CIRCLE ANALYSIS

#### STATION 58+00

Prepared in Office of Division Engineer - Mo. River Div.





NEUMER & SONS, INC. N.Y. NO. 358-11

FORT PECK

6200 U

8400 U

10400 U

12400 U

2200

2400


2600



Berm 1

FACTOR OF SAFETY		
Case I	Case II	Case III
1.2	1.4	1.4


See Fig. 2 For constants used  
in analysis.

**FORT PECK DAM**  
**STABILITY ANALYSIS - UPSTREAM FOUNDATION**  
 SWEDISH METHOD - CIRCLE ANALYSIS  
 STA. 58+00 - WITH UPSTREAM BERM  
 Prepared in Office of Division Engineer - Mo. River Div.





**FORT PECK DAM**  
**STABILITY ANALYSIS - UPSTREAM FOUNDATION**  
**GRAPHICAL ANALYSIS**  
**STATION 58+00**  
 Prepared in Office of Division Engineer - Mo. River Div.



02+00

04+00

06+00

08+00

H

SHELL

CLAYEY FOUNDATION

Under ft of data

Factor of Safety against sliding along base =

$$\frac{W \tan \phi + c}{H} = \frac{5342 \times .18 + 815 \times .15}{1125} = 0.96 \text{ Case I}^*$$

in soil skeleton, = 0.66  
 both in water

core and shell  
 saturated core

$$= \frac{5342 \times .21 + 815 \times .33}{1125} = 1.24 \text{ Case II}^*$$

$$= \frac{5342 \times .24 + 815 \times .12}{1125} = 1.23 \text{ Case III}^*$$

dam = 815 sq ft  
 (Case I\*)

0.18 (Case I\*)


## FORT PECK DAM

## STABILITY ANALYSIS - UPSTREAM FOUNDATION


SLIDE ALONG CLAY FOUNDATION  
 DUE TO CORE PRESSURE

STATION 58+00

Prepared in Office of Division Engineer - Mo. River Div.








FACTOR OF SAFETY		
Case I	Case II	Case III
1.3	1.4	1.4

Sand Foundation  $\tan \phi = 0.65$ ,  $c = 0$   
 See Fig. 2 for other constants  
 used in analysis

**FORT PECK DAM**  
**STABILITY ANALYSIS - UPSTREAM FOUNDATION**  
 SWEDISH METHOD - CIRCLE ANALYSIS  
 STATION 65+00

Prepared in Office of Division Engineer - Mo. River Div.





CROSS SECTION

FORCE DIAGRAM

Scale: 1" = 500'

For Notes, SEE 1

REDFIELD & TOWNSEND, INC. NEW YORK, N.Y.

18 X 24 IN. (11)


PORT PECK

0.00 0.2500 0.5000 0.7500 1.0000



CROSS SECTION

Closure



Factor of Safety 1+

FORCE DIAGRAM

Scale: 1" = 500 Tons

For Notes See Fig. 4


# FORT PECK DAM

## STABILITY ANALYSIS-UPSTREAM FOUNDATION

### GRAPHICAL ANALYSIS

STATION: 65+00

Prepared in Office of Division Engineer, Mo. River Div.



FORT PECK

00 U 4+00 U 6+00 U 8+00 U 10+00

SHELL

Loam  
Sand  
Loam

FACTOR OF SAFETY = 1.9 (All Cases)

Loam Foundation  $\tan \phi = .50, c = 0$

Sand  $\tan \phi = .65, c = 0$


For other constants used in analysis, see Fig. 2


FORT PECK DAM  
STABILITY ANALYSIS-UPSTREAM FOUNDATION  
SWEDISH METHOD-CIRCLE ANALYSIS  
STATION 75+00  
Prepared in Office of Division Engineer, Mo. River Div.


FORT PECK DAM AND RESERVOIR


EMBANKMENT CRITERIA AND PERFORMANCE REPORT

PLATE 4-13









FACTOR OF SAFETY = 2.9 (All Cases)  
 Sand Foundation for  $\phi = 0.65$ ,  $c = 0$   
 See Fig. 2 for other constants used in analysis

**FORT PECK DAM**  
**STABILITY ANALYSIS-UPSTREAM FOUNDATION**  
 SWEDISH METHOD-CIRCLE ANALYSIS  
 STATION 25+00

Prepared in Office of Division Engineer-Mo. River Div.



STA  
0+00


R300

R200

10+00

20+00

30+00



LEGEND


- OLD FOUNDATION HOLES
- NEW FOUNDATION HOLES
- ⊙ HOLES TO BE DRILLED A MIN OF 40' BELOW TOP OF
- 36" CALVE IN FROZEN GROUND EXCEPT HOL.
- 5' CALVE IN FROZEN GROUND
- FAULT
- T STREAM AND GULCH
- ↗ VERTICAL DISPLACEMENT

NOTE: FAULTS IN TUNNEL SHOWN ON CROSS PLANS.  
FAULTS IN TUNNEL OUTLET PIT SHOWN ON SP  
CONTIGUOUS ARE TO BE 2 BARRED WED AT 5' IN  
ELEVATIONS SHOWN AT SOME HOLES ARE OF  
BARRED GULCH

8000


8000

8000



BY SCALE


1. 10000 PLANE  
INTERVAL  
200, 5, 0.4



[illegible]

PLANE AFTER SLIDE  
WHISTLE TURNING AFTER S  
GROUND FILE WHISTLE  
YOUNG GOVS ON FILE COM

FIGURE "B"



## A. GENERAL.

A comprehensive program of laboratory and field tests was made to determine the structural properties of the different types of materials in the damaged area, as well as in unaffected portions of the dam. These tests are grouped as follows:

Tests on overburden materials in the damaged area.

Tests on shell and transition zone material in unaffected portions of the dam.

Tests on typical foundation sands and clays.

Tests on core materials.

Tests on shale and bentonite.

These investigations are each discussed briefly.

**1. Overburden materials in damaged area.** The overburden in the damaged area included both shell and foundation sands, as well as alluvial clays and masses of core material that became intermixed during the movement.

Mechanical analyses for classification purposes were performed on overburden samples from the churn-drill holes. Overburden cores from the Calyx holes were split and photographed, and then samples for laboratory tests were cut from one of the halves. These samples, consisting of 4-inch (102 mm) cubes, were carefully selected and cut to represent typical material from each core. Tests on these included mechanical analyses, specific gravity, moisture content, and determination of the natural voids in the material. The samples were prepared in a cold-storage room, packed with dry ice to keep them frozen, and transported to the laboratory for testing.

Two series of shear tests were made on samples of overburden from Calyx hole No. 4. Plates 5-4 and 5-5 give typical results of tests on overburden materials.

**2. Shell and transition-zone materials in unaffected portions of dam.** Samples of typical shell materials were secured from undisturbed portions of the shell immediately west of the damaged area and from three test pits, located along the 2212 upstream berm, driven down to the saturation line.

A continuous photographic record was kept of the stratification of the material in the deepest test pit. On all samples, the tests included mechanical analyses, specific gravity, relative density (both wet and dry), and determination of natural voids. In addition, triaxial tests were made on disturbed and on several undisturbed samples of typical shell material from one of the test pits.

In order to check the results of critical-density tests performed on the triaxial shear machines, several series of direct-shear tests were also performed and critical density determined by the Taylor method.

Disturbed samples of material from the upstream edge of the core and the upstream edge of the slide were taken from the east transition section. On these samples, mechanical analyses, specific gravity tests, relative density tests, critical-density tests, and shear tests were performed. In the typical tests, a complete mineral analysis was made of a typical sample of shell. Plates 5-6 through 5-13 give results on these materials.

An experimental section of hydraulic fill structure was constructed to investigate the feasibility of this type of material by means of tractors. This fill was placed in 6-in (152 mm), 18-in (457 mm), and 30-in (762 mm) layers to a depth of from 5 feet (1.5 m) to 10 feet (3.0 m). Each layer was compacted by three, six, or nine passes of a 95-horsepower roller operating at half and full speed.

Continuous undisturbed samples were taken from test pits in each sampling area, and mechanical analyses, specific gravity, void determination, relative density tests were made on each. Results on these samples are shown on Plates 5-14 through 5-17.

**3. Foundation sands and clays.** A test pit was driven into the flood plane downstream of the dam in order to secure undisturbed samples of materials similar to the foundation material in the section of the dam affected by the movement. A continuous photographic record of the natural strata in this pit, and mechanical analyses, specific gravity, void determination, relative density and critical-density tests were made on this material.

Undisturbed samples of the surface of the dam were taken at the upstream edge of the damaged area. Mechanical analyses, consolidation tests, and direct-shear tests were performed on them. Plates 5-18 to 5-21 show the results on foundation sands and clays.

**4. Core materials.** At a selected location in the closure section, the undamaged core of the dam, and in the center of the slide (152 mm) drive samples were taken down the center of the core. Mechanical analyses, moisture content, consolidation tests, and consolidation tests were performed on samples from 10-foot intervals in elevation. In addition, triaxial tests, consolidation tests, and direct-shear tests were made on samples from elevation 2080. The results of typical tests on these samples are given on Plates 5-22 to 5-24.

**5. Shale and bentonite.** Samples of

## TESTS OF MATERIALS

shells were taken from the Calyx cores, from the Merriman drift above the inlet portals, and from several points in the damaged area, as well as from five holes and a test pit driven into the weathered shale downstream from the damaged section. Samples of fault-zone material were also secured from the Crosby drift near the shafts. Mechanical analyses, consolidation tests, and both consolidated and quick-shear tests were performed on these samples.

Samples of bentonite were secured from Calyx holes, the Merriman drift, the Crosby drift, and from exposed seams at other points on the right abutment. Both quick and consolidated-shear tests were performed on these samples. The coefficient of friction of bentonite on shale was also determined for some samples. The results of these tests are given on Plates 5-25 to 5-30.

In addition to the laboratory tests on the bentonite, a series of shear tests was made in the field on the two bentonite seams in the Merriman drift. These seams were lying approximately horizontal and were separated by 3 inches (203 mm) of shale. Both the normal loads and shearing loads were applied by means of hydraulic jacks. The center section of shale was confined by a steel jacket, to prevent its being crushed by the vertical load and to properly distribute the shearing forces.

### B. EQUIPMENT AND PROCEDURE FOR LABORATORY TESTS.

1. Mechanical analyses. All mechanical analyses were made by the sieve and hydrometer method and were usually run wet. Samples composed of distinctly different types of material, such as sand with quantities of shale fragments or clay balls and clay samples mixed with gravel, were segregated and the percentage of each kind of material determined separately. These samples were run dry.

2. Specific-gravity determinations. Specific-gravity determinations were made on material from every sample, so that void determinations could be made more accurately. Specific-gravity determinations were made by the vacuum method on 200-gram samples.

3. Void determinations. For the purpose of determining the natural void ratio in undisturbed samples of materials from the shells, transition zones, foundation sands, and the experimental rolled hydraulic fill, 6-inch-diameter (152 mm) samples were taken in accurately calibrated cylinders 6 inches (152 mm) in length.

Void determinations of material from the frozen Calyx cores were made on the 4-inch (102 mm) cubes. The volume of the cubes was accurately determined by submerging them in a pan filled to the overflow with mercury and weighing the mercury displaced.

4. Relative-density tests. Relative-density tests

were performed on all undisturbed samples of shell material, transition-zone material, and sandy material from the test pit in the flood plane below the dam, as well as on all samples from the experimental rolled hydraulic fill. The large number of relative-density tests made it necessary to construct a special device for compacting the samples to maximum density. This apparatus consisted of several pedestals, on which the tubes containing the samples were placed, the pedestals and samples being jarred up and down by cams on a motor-driven shaft. For determining the lowest possible degree of compaction, the materials were carefully deposited in glass cylinders through specially designed funnels. Relative-density tests were made on each sample in both dry and saturated condition.

5. Critical-density tests. Critical-density tests on shell materials were performed in the soils laboratory of the Graduate School of Engineering of Harvard University, at the Waterways Experiment Station, Vicksburg, Miss., and at the Fort Peck District laboratory. Tests on undisturbed samples of cohesionless materials were made at the Fort Peck laboratory.

6. Consolidation tests. All consolidation tests were made according to standard procedure in the Fort Peck type of consolidation equipment. Samples were all 5-5/8 inches (143 mm) in diameter. Samples of transition-zone material and the more pervious samples of core material were 2-1/2 inches (64 mm) in thickness, while samples of very impervious materials, such as clays and weathered shale, were 1.0 inch (25 mm) or 1-1/4 inches (32 mm) thick.

Consolidation of core and a few weathered-shale samples prior to making shear tests was accomplished in consolidation devices, although most of the bentonite and weather-shale samples were preconsolidated directly in the shear boxes.

7. Shear tests. Consolidated-shear tests on transition-zone material, weathered shale and bentonite were made in the M.I.T. shear machine, while the direct-shear tests on shell material and tests on core material were made in the Zanesville-type shear machine. All quick-shear tests were made in the Zanesville-type shear machine. The shear test samples were 4 inches (102 mm) square and 3/4-inch (10 mm) thick.

Consolidated shear tests were made by first consolidating the sample to the desired load and then adding the shearing loads in increments and waiting until movement ceased before adding additional load increments. Quick-shear tests were made with constant strain loading, the load being applied continuously, so that failure occurred within a few minutes after start of the test.

undisturbed samples of shell material, and sandy material in the flood plane below the samples from the experimental. The large number of relative necessary to construct a specting the samples to maximum consisted of several pedestals containing the samples were and samples being jarred up motor-driven shaft. For determinable degree of compaction, the samples deposited in glass cylinder designed funnels. Relative on each sample in both dry

Tests. Critical-density tests performed in the soils laboratory School of Engineering of the Waterways Experiment Station, and at the Fort Peck Districts on undisturbed samples of were made at the Fort Peck

Tests. All consolidation tests to standard procedure in the consolidation equipment. Samples (143 mm) in diameter. Samples material and the more pervious material were 2-1/2 inches (64 mm) samples of very impervious material and weathered shale, were 1/4 inches (32 mm) thick.


and a few weathered-shale shear tests was accomplished tests, although most of the bench samples were preconsolidated in shear boxes.

Consolidated-shear tests on material, weathered shale and in the M.I.T. shear machine, tests on shell material and were made in the Zanesville quick-shear tests were made in shear machine. The shear (102 mm) square and



tests were made by first consolidating the desired load and then adding in increments and waiting before adding additional load. Tests were made with consolidation load being applied continuously occurred within a few minutes of the test.

3





### MECHANICAL ANALYSIS CURVE OF SOIL TESTED




### VERTICAL AND HORIZONTAL MOVEMENT CURVES DURING TEST



# HORIZONTAL PRESSURE IN TONS/SQ FT VERTICAL AND HORIZONTAL MOVEMENT CURVES DURING TEST


MOISTURE CONTENT  
PERCENT DRY WEIGHT



## LEGEND-M.C.

Before Test	○
Undist.	○
After Test	△

SHEARING RESISTANCE TONS/SQ FT



## LEGEND

△	1 T/sq. ft.
□	2 T/sq. ft.
○	3 T/sq. ft.
+	4 T/sq. ft.
●	5 T/sq. ft.

# VERTICAL LOAD TONS/SQ FT NORMAL LOAD-SHEARING RESISTANCE CURVE

Notes: Undisturbed Sample  
Consolidated Shear Tests  
Increment Loading  
Elevation 2047.0-2048.6  
Gross Sectional Area of Sample 16.00 sq. in.  
Initial Thickness = 1.00 inch  
Sample Immersed in Water During Test.  
Station 14+79.0 Range 0/87U  
Section # 39

Shearing Resistance  
Cohesion (Tons/Sq Ft)  
= 0.552

$\phi = 28^{\circ}54'$

$C = Cohesion = 0.08/eq. ft.$

MISSOURI RIVER IMPROVEMENT  
NATIONAL FLOOD CONTROL, POWER, IRRIGATION

## FORT PECK DAM



SLIDE INVESTIGATION  
CONSOLIDATED SHEAR TESTS SERIPTS # 1\*  
MIXED MATERIAL FROM CALIX HOLE # 4




Drawn by	JLB	Checked by	JLB	Reviewed by	JLB
Date	10/1/54	Date	10/1/54	Date	10/1/54
Scale	1" = 10'	Scale	1" = 10'	Scale	1" = 10'

**CALYX HOLE NO. 4—STATION 14+79, RANGE 0+87-U**  
(Original sheets 2 and 3)

Core No.	Elevation top of core	Specific gravity	Moisture content, percent	Void ratio "E"	Percent of voids
1.....	2,124.30	2.697	25.7	0.783	43.9
2.....	2,122.00	2.693	20.7	.627	38.5
3.....	2,119.70	2.701	21.5	.676	40.3
4.....	2,118.30	2.689	21.5	.635	38.8
5.....	2,116.50	2.693	19.3	.564	36.1
6.....	2,114.30	2.704	20.2	.603	37.6
7.....	2,112.90	2.684	21.1	.624	38.4
8.....	2,110.72	2.691	20.6	.601	37.5
9.....	2,108.90	2.690	17.6	.512	33.8
10.....	2,107.20	2.692	18.7	.542	35.1
11.....	2,105.59	2.712	17.1	.509	33.7
12.....	2,103.88	2.682	20.7	.604	37.7
13.....	2,101.39	2.677	23.9	.731	42.2
14.....	2,099.29	2.680	22.2	.696	41.0
15.....	2,097.36	2.675	21.5	.665	40.0
16 <sup>1</sup> .....	2,095.20				
17.....	2,092.70	2.676	22.6	.670	40.1
18.....	2,090.60	2.678	21.6	.645	39.2
19.....	2,088.57	2.664	22.0	.637	38.9
20.....	2,086.71	2.688	22.1	.654	39.5
21.....	2,085.20	2.690	20.7	.619	38.2
22.....	2,082.70	2.665	21.2	.607	37.8
23.....	2,080.74	2.675	23.8	.723	42.0
24.....	2,078.81	2.714	19.3	.708	41.5
25.....	2,077.25	2.694	21.0	.644	39.2
26.....	2,074.94	2.669	21.6	.650	39.4
27A.....	2,072.90	2.685	21.6	.674	40.3
B.....		2.691	21.7	.685	40.6
28.....	2,071.43	2.680	22.4	.673	40.2
29.....	2,069.20	2.703	19.2	.570	36.3
30.....	2,067.50	2.690	21.4	.639	39.0
31.....	2,064.90	2.692	21.4	.643	39.1
32.....	2,062.70	2.691	21.8	.648	39.3
33.....	2,061.00	2.697	21.7	.635	38.9
34.....	2,058.60	2.677	22.7	.666	39.9
35.....	2,056.10	2.692	21.4	.619	38.2
36.....	2,054.46	2.689	19.6	.568	36.2
37.....	2,052.20	2.688	19.1	.566	36.1
38.....	2,050.00	2.680	19.3	.551	35.5
39.....	2,048.90	2.743	26.6	.824	45.2
40.....	2,046.30	2.752	29.5	.680	40.5
41.....	2,043.60	2.697	28.3	.867	46.4
42.....	2,041.10	2.701	24.1	.750	42.8
43.....	2,039.70	2.727	22.7	.711	41.6

<sup>1</sup> First half destroyed, no sample obtained from other half of core.








LEGEND-M.C.		
Before Test	○	Initial
After Test	△	-----

LEGEND	
A	1 T/0
□	3 T/0
○	5 T/0
+	9 T/0
●	—

[illegible]





**PRESSURE-VOID RATIO CURVE**  
Estimated Previous Consolidation -  $\frac{\text{Tons}}{\text{Sq. Ft.}}$

Undisturbed Sample Immersed in Water during test  
Station 41 + 00; Range 0 / 26-U  
Initial Thickness 2.50 inch  
Gross Sectional Area 24.80 sq. in.  
Elevation 47.2; Depth 8'

VERTICAL LOAD TONS/SQ. FT.	COMPACTION PERCENT *
0.00	0.00
0.07	1.76
1.00	3.07
4.00	4.68
8.00	5.82
12.00	6.80
6.00	6.67
0.07	5.45

\* Total compaction in percent of original height of sample.


MISSOURI RIVER IMPROVEMENT  
NAVIGATION, FLOOD CONTROL, POWER, IRRIGATION

**FORT PECK DAM**  
SLIDE INVESTIGATION  
CONSOLIDATION TEST, TRANSITION MATERIAL  
TEST PIT NO. 5; SERIES #1

U.S. ENGINEER OFFICE, FORT PECK, MONT.


Submitted	Approval Recommended	Approved
Drawn by	Checked by	Transmitted with report
DNS	ERG	dated

Major Corps of Engineers  
Civil Corps  
Transmitted with report







2




ITEM	RANGE OF VALUES
SPECIFIC GRAVITY	2.68 - 2.70
EFFECTIVE SIZE	0.11 - 0.24


FORT PECK DAM  
 RELATIVE DENSITY TESTS  
 TRANSITION ZONE MATERIAL  
 TEST PIT 5






FORT PECK DAM  
TYPICAL VOID RATIO CURVES FOR  
REMOLDED SAMPLES  
TRANSITION ZONE MATERIAL  
TEST PIT 5







FORT PECK DAM  
TYPICAL VOID RATIO CURVES FOR  
UNDISTURBED AND REMOLDED SAMPLES  
SHELL MATERIAL  
TEST PIT 3



FORT PECK DAM  
RELATIVE DENSITY TESTS  
SHELL MATERIAL  
TEST PIT 1



ITEM	RANGE OF VALUES
SPECIFIC GRAVITY	2.68 - 2.73
EFFECTIVE SIZE	0.11 - 0.21





**PETROGRAPHIC ANALYSIS OF SAND SAMPLE, FORT PECK,  
NO. 1-A**

**General Statement.** The usual procedure in the petrographic analysis of a sand is to separate the sample into two fractions on the basis of the specific gravity of the constituents. The "light" fraction (sp. gr. less than 2.84) contains most of the material, but the "heavy" fraction (sp. gr. greater than 2.84) contains a greater variety of minerals. The percentage of each fraction is determined by weight, but the percentages of minerals and other constituents within each fraction is determined by counting grains, and hence is a frequency percentage, not a weight percentage. This procedure does not introduce any great error if the grains are fairly uniform in size, but in the present sample they are not. The grains range from fine gravel to clay size, so that frequency percentages determined on the whole sample would place an unwarranted emphasis on the minute grains, which are numerically abundant but constitute only a small percentage by weight of the whole sample. Since the various size grades of this sample show marked differences in composition, this factor is important, especially in the case of "light" fraction, which constitutes 97 percent of the sample. To eliminate this error it would be necessary to analyze each size grade, then multiply the percentage of each mineral in each size grade by the weight percentage of the size grade as determined by mechanical analysis (sieving). Totalling the products for each mineral would give its weight percentage in the sample as a whole, except for minor errors resulting from differences in the specific gravities of the minerals. This procedure, however, greatly increases the time required for an analysis, and hence would increase its cost considerably over the price quoted in the contract for analysis of this sample. I have therefore done the next best thing - analysed the "light" fraction of the two size grades which contain the greatest amount of the sample, the 35 to 48 mesh and 48 to 65 mesh grades. I have also included an analysis of the coarsest grade (.8 to 14 mesh) and an estimate of the composition of the finest material (passing the 200 mesh sieve). The "heavy" fraction constitutes such a small percentage (3 percent) of the whole sample that this procedure was not considered necessary.

**Composition of the "light" fraction.** The "light" fraction comprises 0.97 percent of the sample. The two size grades containing most of the material have the following composition:

**Composition of the "light" fraction of the 35 to 48 and 48 to 65 mesh size grades.**

(Frequency percentages on the basis of 100 percent)

	35-48 size grade	48-65 size grade
<b>Rock grains:</b>		
Chert	14	15
Shale	11	10
Sandstone and siltstone	6	3
Volcanic rocks	11	10
Granitic rocks	3	2
	45	40
Quartz	38	45
<b>Feldspars:</b>		
Plagioclase	10	8
Microcline	3	3
Orthoclase	2	2
Sandline	P	P
	15	13
<b>Others:</b>		
Muscovite	P	P
Chlorite	P	P
Calcite	P	1
Volcanic glass	1	P
Carbonaceous material (lignite) P		P
	2	2

**NOTE - P = Present in amounts less than 1 percent.**

The coarsest size grade (8-14 mesh), has the following composition: Rock grains 82 percent (chert 2 percent, shale 52 percent, sandstone and siltstone 26 percent, volcanic rocks 1 percent, granitic rocks 1 percent), quartz 10 percent, feldspars 5 percent, calcite 2 percent, volcanic glass and lignite in traces.

Percentages were not determined on the finest material (passing the 200 mesh), but inspection indicates that it has approximately the following composition: calcite 15-20 percent, clay mineral aggregates 15-20 percent, quartz and feldspar (together) 55-65 percent, others about 5 percent.

**Composition of the "heavy" fraction.** The "heavy" fraction constitutes 3 percent of the sample. About half of this material consists of the iron oxides, limonite and hematite. These occur as grains up to 3 mm in diameter, and their presence in such abundance so interfered with determination of the other

minerals  
by boiling  
for 10 m  
gite is  
in grains  
other "h  
percenta  
its frequ

**Compositi  
sample.**

Soluble  
Chiefly  
cent  
and at  
Insoluble  
(Frequ  
Opaque M  
limonite  
Leucos  
Magne  
Pyrite  
Amphibole  
Actinolite  
Basalt  
Blue-  
Common  
Micas:  
Biotite  
Muscovite  
Pyroxene  
Augite  
diorite  
Hypersthene

It was found necessary to remove them the "heavy fraction" in 50 percent HCl. Of the material not removed, augite is the most common mineral, occurring to 3 mm in length. Since most of the minerals are much smaller, the weight of augite is considerably higher than percentage.

Composition of the "heavy" fraction from the whole sample, continued.

50 percent HCl 50% by wt.  
 Monite and hematite, with 1 to 2 percent the carbonates dolomite and siderite, 1 percent apatite.  
 50 percent HCl.  
 Percentages on basis of 100 percent.)

Others:


Allanite	P
Barite	8
Collophane	P
Epidote	9
Garnet	6
Rutile	P
Staurolite	P
Titanite	2
Tourmaline	P
Zircon	3
Zoisite	P


Note - P = Present in amounts less than 1 percent.


hornblende  
 hornblende  
 blende  
 including some aegirine-augite and


Conclusions. The abundance of shale fragments in the coarser size grades indicates contribution of this material from a nearby source, as these fragments could not withstand prolonged transportation. The other elements in the sample have been derived chiefly from intermediate to basic volcanic rocks (andesites and basalts), as indicated by the abundance of augite as well as of fragments of these rocks, and from previously formed sedimentary rocks. Other igneous rocks, particularly granitic types, have contributed some material, while metamorphic rock types furnished very little.

[s] R. DANA RUSSELL.











ITEM	RANGE OF VALUES
SPECIFIC GRAVITY	2.68 - 2.72
EFFECTIVE SIZE	0.11 - 0.19

FORT PECK DAM  
RELATIVE DENSITY TESTS  
EXPERIMENTAL ROLLED HYDRAULIC FILL  
(TEST PIT C-3)








ITEM	RANGE OF VALUES
SPECIFIC GRAVITY	2.67 - 2.71
EFFECTIVE SIZE	0.13 - 0.21

FORT PECK DAM  
 RELATIVE DENSITY TESTS  
 EXPERIMENTAL ROLLED HYDRAULIC FILL  
 (TEST PIT C-X)












MECHANICAL ANALYSIS CURVE OF SOIL TESTED




VERTICAL AND HORIZONTAL MOVEMENT CURVES DURING TEST

HORIZONTAL



VERTICAL




# VERTICAL AND HORIZONTAL MOVEMENT CURVES DURING TEST

LEGEND-M.C.	
Before Test	○ Undist.
After Test	△

MOISTURE CONTENT PERCENT DRY WEIGHT

LEGEND	
△	1 T/24 ft.
□	2 T/24 ft.
○	3 T/24 ft.
+	4
●	AVER
M.A. Grading & tests	
TENS. SHEAR SERIES # 1	

SHEARING RESISTANCE TONS/SQ FT



## NORMAL LOAD-SHEARING RESISTANCE CURVE

Notes: Undisturbed Sample

Quick Shear Tests  
Constant Strain Grading  
Elevation 2052.1-2052.5  
Depth 45.2-45.7  
Cross section: Area of Sample 18.00 sq. ft.  
Initial void ratio 0.81  
Vertical load-shearing resistance curve  
Vertical load-shearing resistance curve

Shearing Resistance  
Cohesion (tons/sq ft)  
C = Cohesion = 0.30 T/sq ft.

φ = 28°55'

C = Cohesion = 0.30 T/sq ft.

MISSOURI RIVER IMPROVEMENT  
FLOOD CONTROL, POWER, IRRIGATION

## FORT PECK DAM


SLIDE INVESTIGATION

Quick Shear Tests-Series # 3


SURFACE CLAY-HOLE-11 Sample # 2

APPROVED	APPROVED
APPROVED	APPROVED
APPROVED	APPROVED
APPROVED	APPROVED





TIME-PERCENT CONSOLIDATION CURVES



PRESSURE-VOID RATIO CURVE

Estimated Previous Consolidation - Tons/Sq.Ft.

Undisturbed Sample Immersed in Water during test  
 Station 27 / 16, Range 22 / 22-U  
 Initial Thickness 1.00 inch  
 Cross Sectional Area 24.80 sq. in.  
 Elevation - 2051.8 - Depth 46.5'

VERTICAL LOAD TONS/SQ.FT.	COMPACTION PERCENT
0.00	0.00
0.07	0.00
1.00	5.58
4.00	14.10
8.00	19.11
12.00	21.75
16.00	21.92
20.07	10.17

\* Total compaction in percent of original height of sample

MISSOURI RIVER IMPROVEMENT  
 NAVIGATION, FLOOD CONTROL, POWER, IRRIGATION

FORT PECK DAM

SLIDE INVESTIGATION  
 CONSOLIDATION TEST SURFACE CLAY  
 HOLE C-11, SAMPLE NO. 3


U.S. ENGINEER OFFICE, FORT PECK, MONT. 1-13-39

Submitted: \_\_\_\_\_ Approved: \_\_\_\_\_

Checked by: \_\_\_\_\_



Drawn by: \_\_\_\_\_

WA dated: \_\_\_\_\_





FORT PECK DAM  
TYPICAL CRITICAL VOID RATIO TESTS  
ON FOUNDATION SANDS
















VERTICAL AND HORIZONTAL MOVEMENT CURVES DURING TEST

**LEGEND-M.C.**  
 Before Test ○ Distort.  
 After Test △





**LEGEND**  
 △ --- = 1 T/q.ft.  
 □ --- = 3 T/q.ft.  
 ○ --- = 5 T/q.ft.  
 + --- =  
 ● --- =




NORMAL LOAD-SHEARING RESISTANCE CURVE


Notes: Undisturbed Sample  
 Quick Shear Tests  
 Constant Strain Loading  
 Maximum rate of horizontal movement 0.021"/min  
 Elevation 2226.8 - 2226.3  
 Depth 20.9 - 21.4  
 Cross Sectional Area of Sample 16.00 sq. in.  
 Initial Thickness 0.75 inch.  
 Sample Immersed in Water during test  
 Station 60; Range 0 + 35-D  
 $c = \text{Cohesion} = 0.0 \text{ T/sq.ft.}$   
 $\phi = 29^\circ$   
 $\text{Temp} = \frac{\text{Shearing Resistance}}{\text{Vertical Load}} = \frac{\text{Cohesion (tons/sq.ft.)}}{\text{Vertical Load (tons/sq.ft.)}} = 0.584$

MISSOURI RIVER IMPROVEMENT  
 NATIONAL FLOOD CONTROL DISTRICT  
**FORT PECK DAM**  
 SLIDE INVESTIGATION  
 QUICK SHEAR TESTS - CORE MATERIAL  
 HOLE C-7, SAMPLE #5, SERIES #1  
 THIS SHEET WAS PREPARED BY: [ ]  
 CHECKED BY: [ ]  
 DATE: [ ]  
 JLB EBC





TIME-PERCENT CONSOLIDATION CURVES



PRESSURE-VOID RATIO CURVE

Estimated Previous Consolidation = Tons/Sq. Ft.

Undisturbed sample  
 Immersed in water during test  
 Station 60 + 00 Range 0 + 35D  
 Depth 13.5 Elev. 2234.2  
 Initial Thickness 2.50"  
 Cross Sectional Area of sample 24.8 sq. in.  
 Natural Moisture Content 23.0%  
 \* Total compaction in percent of original height of sample



VERTICAL LOAD TONS/SQ. FT.	COMPACTION PERCENT*
0.07	0.58
0.56	3.34
1.00	4.00
4.00	6.71
8.00	8.22
12.00	9.70
6.00	9.60
0.07	8.65

MISSOURI RIVER IMPROVEMENT  
 NAVIGATION, FLOOD CONTROL, POWER, IRRIGATION

**FORT PECK DAM**

SLIDE INVESTIGATION  
 CONSOLIDATION TESTS ON CORE MATERIAL  
 HOLE C-7 - SAMPLE #2  
 U.S. ENGINEER OFFICE, FORT PECK, MONT. 12-13-36

Submitted: \_\_\_\_\_ Approved: \_\_\_\_\_  
 Checked by: \_\_\_\_\_  
 Drawn by: \_\_\_\_\_  
 PMS REC. OA




AD-A123 608

EMBANKMENT CRITERIA AND PERFORMANCE REPORT MISSOURI  
RIVER FORT PECK LAKE MONTANA VOLUME II DRAWINGS(U) ARMY  
ENGINEER DISTRICT OMAHA NEBR SEP 82


2/2

UNCLASSIFIED

F/G 13/13 NL






END  
DATE  
FILMED  
8-83  
DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A





LEGEND-M.C.

Before Test	○
After Test	△
Undisturbed	□

LEGEND

△	5 T/4. ft.
□	7 T/4. ft.
○	9 T/4. ft.
+	11 T/4. ft.
●	13 T/4. ft.

VOID RATIO BEFORE AND AFTER TEST

Values typed above and below plotted shearing resistance at ultimate failure denote void ratio before and after shear tests respectively.

VOID RATIO COMPUTED FROM THICKNESS DATA

**NORMAL LOAD-SHEARING RESISTANCE CURVE**

Notes

- Undisturbed Sample
- Consolidates shear tests
- Delta Loading
- Gross Sectional Area of Sample 10.00 sq. in
- Initial Thickness 0.75 inch
- Sample Immersed in Water During Test
- Note: Sample taken from block of soft shale in weathered zone in drift above inlet portals.

Shearing Resistance  
 $\frac{\text{Cohesion (tons/sq. ft.)}}{\text{Vertical Load (tons/sq. ft.)}} = 0.294$

$\phi = 16^{\circ} 25'$

$c = \text{Cohesion} = 0.07 \text{ tons/sq. ft.}$

**FORT PECK DAM**

**SLIDE INVESTIGATION**


**CONSOLIDATED SHEAR TESTS SERIES # 1\***

**UND. WEATHERED SHALE--INLET PORTALS.**


**MISSOURI RIVER IMPROVEMENT**

DESIGNED BY: [Signature] CHECKED BY: [Signature] APPROVED BY: [Signature]


DATE: [Date]




# **MECHANICAL ANALYSIS CURVE OF SOIL TESTED**



2



TIME-PERCENT CONSOLIDATION CURVES



PRESSURE-VOID RATIO CURVE

Estimated Previous Consolidation = ... Tons/Sq. Ft.  
 Undisturbed sample of weathered shale from  
 Merriman Drift above Inlet Portals.  
 Immersed in water during test.  
 Initial Thickness 1.25 inches.  
 Cross Sectional Area 24.80 sq. in.

VERTICAL LOAD TONS/SQ. FT.	COMPACTION PERCENT
0.00	0.00
8.00	0.08
4.00	0.80
8.00	1.88
12.00	2.04
6.00	2.24
0.07	- 1.86

\* Total compaction in percent of original height of sample.

MISSOURI RIVER IMPROVEMENT  
 NAVIGATION, FLOOD CONTROL, POWER, IRRIGATION



FORT PECK DAM


SLIDE INVESTIGATION  
 CONSOLIDATION TEST WEATHERED SHALE  
 MERRIMAN DRIFT; SAMPLE #1

U.S. ENGINEER OFFICE, FORT PECK, MONT. 1-80-88


Submitted: \_\_\_\_\_ Approval Recommended: \_\_\_\_\_ Approved: \_\_\_\_\_

Drawn by: DWS JBC  
 Checked by: \_\_\_\_\_  
 Title: \_\_\_\_\_  
 File No. \_\_\_\_\_






HORIZONTAL PRESSURE IN TONS/SQ. FT.  
VERTICAL AND HORIZONTAL MOVEMENT CURVES DURING TEST



MOISTURE CONTENT  
SHEARING RESISTANCE TONS/SQ. FT.



VERTICAL LOAD TONS/SQ. FT.  
NORMAL LOAD-SHEARING RESISTANCE CURVE

Notes: Undisturbed Sample  
Consolidated Shear Tests  
Incremental Loading  
Elevation 2115.0 - 2114.0  
Depth 0.0 - 1.0  
Cross Sectional Area of Sample 10.00 Sq. In.  
Initial Thickness 0.75 inch  
Sample immersed in water during test  
Station 13 / 5 Range 14 / 5U

$\phi = 18^\circ 25'$   
 $c = \text{Cohesion} = 0.80 \text{ T/sq.ft.}$

Shearing Resistance  
 $\frac{\text{Cohesion (tons/sq.ft.)}}{\text{Vertical Load (tons/sq.ft.)}} = 0.278$

LEGEND-M.C.	
Before Test	○
After Test	△
Undisturbed	□

LEGEND	
△	1 T/sq.ft.
□	3 T/sq.ft.
○	5 T/sq.ft.
+	7 T/sq.ft.
●	9 T/sq.ft.

MISSOURI RIVER IMPROVEMENT  
NAVIGATION, FLOOD CONTROL, POWER, IRRIGATION

**FORT PECK DAM**  
SLIDE INVESTIGATION  
SHEAR TESTS ON UNDISTURBED SAMPLES OF  
DISTURBED WEATHERED SHALE

U.S. ENGINEER OFFICE, FORT PECK, MONT 1-4-38

Approved: \_\_\_\_\_  
Checked by: JLB EBC  
Drawn by: JLB EBC  
Date: \_\_\_\_\_

Results of tests on undisturbed samples of shale taken in the Fort  
Peck Dam Foundation, downstream, with 6-inch sampler

(Original sheets 30-31)

1	2	3	4	5	6	7	8	9
Sample No.	Sam- ple depth in feet	Depth into shale in feet	Equi- valent load in tons/ sq. ft.	Mois- ture content, percent dry weight	Shearing strength in tons/ sq. ft.	Computed shearing strength tons/sq. ft. with Tan $\phi = 18$ , C = .20	Ratio $\frac{6}{7}$	Type test
HOLE C-12 STATION 10+75, RANGE 8+00 D								
6.....	14.6	1.4	0.53	31.3	0.43	0.35	1.85	Quick.
7.....	14.6	3.4	.97	22.8	.85	.37	2.32	Consol.
8.....	14.6	5.4	1.89	23.3	.89	.40	2.2	Quick.
9.....	14.6	7.4	1.21	20.6	.84	.42	1.94	Quick.
HOLE C-13 STATION 12+00, RANGE 8+00 D								
2.....	24.5	6.0	1.39	26.6	1.39	0.43	2.9	Quick.
3.....	24.5	8.0	1.29	27.7	1.09	.44	2.5	Consol.
4.....	24.5	2.0	1.44	45.5	.94	.45	2.1	Quick.
5.....	24.5	4.0	1.53	25.0	2.00	.46	4.3	Quick.
6.....	24.5	6.0	1.06	25.5	1.13	.39	2.3	Quick.
7.....	24.5	8.0	1.65	28.0	1.35	.39	3.1	Consol.
8.....	24.5	10.4	1.90	25.0	1.23	.54	2.3	Quick.
9.....	24.5	12.0	2.01	26.0	1.26	.56	2.3	Quick.
HOLE C-14 STATION 12+00, RANGE 8+00 D								
2.....	46.3	1.7	2.48	20.0	2.25	0.65	3.5	Quick.
3.....	46.3	3.7	2.60	24.5	1.30	.67	1.9	Consol.
4.....	46.3	5.7	2.72	21.2	2.4	.69	3.5	Quick.
5.....	46.3	7.7	2.84	20.2	1.98	.71	2.7	Quick.
6.....	46.3	18.3	3.18	23.5	1.50	.77	1.96	Quick.
HOLE C-15 STATION 13+25, RANGE 8+00 D								
2.....	71.5	2.0	3.87	25.5	1.39	0.90	1.55	Quick.
3.....	71.5	3.5	3.96	25.7	1.51	.92	1.64	Consol.
4.....	71.5	7.75	4.21	25.5	2.59	.96	2.7	Quick.
7.....	71.5	11.75	4.46	25.0	2.05	1.05	1.96	Quick.
HOLE C-16 STATION 14+40, RANGE 8+00 D								
2.....	100	1.0	5.78	27.7	2.54	1.26	2.04	Quick.
3.....	100	3.0	5.90	27.1	3.02	1.26	2.40	Consol.
4.....	100	7.0	6.16	28.8	1.89	1.39	1.45	Quick.
TEST SHAFT, STATION 15+00, RANGE 8+00 D								
0.....	24.5	1.3	1.36	28.1	0.73	0.44	1.64	Quick.
1.....	24.5	1.3	1.36	34.1	.94	.44	2.13	Quick.
2.....	24.5	3.3	1.73	28.2	1.44	.53	2.77	Quick.
GLACIAL TILL FROM HOLE AT STATION 106+00, RANGE 0+00 D								
3.....	40.5	3.5	2.34	13.7	1.30	0.53	1.64	Quick.
4.....	40.5	5.5	2.46	19.6	1.54	.56	1.82	Quick.
5.....	40.5	7.5	2.58	28.4	1.49	.59	1.57	Consol.
6.....	40.5	9.5	2.70	27.8	1.44	.59	1.57	Quick.

<sup>1</sup> After test.




NOTE.—Except for samples 1 and 2 from the test shaft all samples were 6" drive samples.


Duration of test for Quick shear varied from 1.5 to 3 minutes.

The vertical load for the duration of the test was as indicated in Column 4.

Tan  $\phi = 0.18$ , C = 0.20 were coefficients used in the design of the reconstruction in the slide area.

For computed shearing strength for Glacial Till from Hole S. D. 106/9.96 coefficients used were Tan  $\phi = .25$ , C = .23.





HORIZONTAL PRESSURE IN TONS/SQ. FT.  
VERTICAL AND HORIZONTAL MOVEMENT CURVES DURING TEST



NORMAL LOAD-SHEARING RESISTANCE CURVE

Notes:

- Shearing Resistance
- $\tan \phi = \frac{\text{Cohesion (tons/sq. ft.)}}{\text{Vertical Load (tons/sq. ft.)}}$
- $\phi = 6^\circ 50'$
- $c = \text{Cohesion} = 0.80 \text{ t/sq. ft.}$
- Undisturbed Sample
- Consolidated Shear Tests
- Increment Loading
- Gross Sectional Area 16.00 sq. in.
- Initial Thickness 0.76 inch.
- Sample Immersed in Water during Test.

LEGEND-M.C.	
Before Test	○
After Test	△
Undisturbed	□

LEGEND	
△	— = 8 7/8 sq. ft.
□	— = 8 7/8 sq. ft.
○	— = 10 7/8 sq. ft.
+	— = 12 7/8 sq. ft.
●	— = 15 7/8 sq. ft.

MIS. O. R. RIVER IMPROVEMENT  
SLIDE INVESTIGATION  
FORT PECK DAM  
CONSOLIDATED SHEAR TESTS - SERIES #1  
REYNOLDS FROM CROSSY DRIFT  
1-27-39

JTB EBC



# LEGEND

A	11.5 YOUNG/MQ. FT.
D	11.5 YOUNG/MQ. FT.
Q	11.5 YOUNG/MQ. FT.
T	11.5 YOUNG/MQ. FT.
U	11.5 YOUNG/MQ. FT.

Notes: Undisturbed Sample from Harrison Drift above Inlet Portals  
Quick Shear Tests  
Moisture content of Shales 17.5% (over Fair Gravel)  
Moisture content of Bentonite = 44.5% (over Fair Gravel)  
Sample Immersed in Water during test.  
Initial Thickness of Sample = 1.00 inch  
Cross Sectional Area of Sample = 16.00 sq. in.

WATER = 0.125  
IN.  $\phi$  10"  
OR 0.60 P/MQ. FT.

12 IN. DIA. SHAFT - REMAINING TESTED

11 12 13 14 15

MISSOURI RIVER IMPROVEMENT

## FORT PECK DAM

SLIDE INVESTIGATION

QUICK SHEAR TESTS SERIES # 1

BENTONITE STRAM ON SHEET NO.

SCALE:

U. S. ENGINEER OFFICE FORT PECK, MONTANA

Submitted: Approved: Recommended: Approved:

Major Corps of Engineers Major Corps of Engineers

Issued by: Submitted with report File No.

J. E. E. B. G. 1-7-30

VERTICAL LOAD - TON PER SQ. FT.

HORIZONTAL MOMENT IN INCHES

FIGURE 16.—Results of shear tests.

All tests are consolidated unless otherwise noted

Transition zone material:

Tan $\phi$	c
0.712	0.0
0.640	0.0

Stratified material from Calyx No. 4:

Tan $\phi$	c
0.520	0.0

Bentonite from Merriman drift:

Tan $\phi$	c
0.136	0.40

Bentonite from Crosby drift:

Tan $\phi$	c
0.155	0.20

Bentonite from Calyx No. 8 (Hard, impure bentonite, considerable volcanic ash):

Tan $\phi$	c
0.247	0.90

Bentonite from near outlet portals:

Tan $\phi$	c
0.241	0.70

Bentonite from Calyx No. 2:

Tan $\phi$	c
0.139	0.80

Shale and bentonite from Calyx No. 4 (Sample consisted of fractured shale with the fractures filled with thin seams of bentonite):

Tan $\phi$	c
0.180	0.80

Bentonite on shale (Field test material):

Quick shear	
Tan $\phi$	c
0.120	0.0
0.126	0.4

Weathered shale:

a. Undisturbed sample of disturbed weathered shale in slide area:

Consolidated		Quick shear	
Tan $\phi$	c	Tan $\phi$	c
0.234	0.28	0.037	0.34
0.275	0.30	0.037	0.30
0.205	0.20	0.291	0.40

b. Gouge material from Crosby drift:

Tan $\phi$	c
0.182 (quick shear)	0.20
0.210 (consolidated)	0.50

c. Sample taken from block of soft shale from weathered zone in Merriman drift at inlet portals:

Tan $\phi$	c
0.302	0.40
0.282	1.00
0.294	0.00

d. Field Shear Test. Shale on bentonite.

Tan $\phi$	c
0.151	0.05

e. Weathered shale from Calyx No. 2:

Tan $\phi$	c
0.262	0.00

f. Undisturbed weathered shale from Calyx No. 3:


Tan $\phi$	c
0.298	0.20

Surface clay:

Consolidated		Quick shear	
Tan $\phi$	c	Tan $\phi$	c
0.210	0.40	0.067	0.25
0.153	0.50	0.014	0.41
0.158	0.50	0.014	0.40
		0.050	0.20
		0.051	0.31

CORE MATERIAL

Hole	Sample	Tan $\phi$	Cohesion
C-7-----	3	0.633	0.0
	4	.702	0.0
	5	.564	0.0
	6	.675	0.0
	8	.694	0.0
	18	.579	0.0
	19	.787	0.0
	22	.698	0.0
	28	.696	0.0
	36	.367	0.15
	40	.616	0.00
	45	.656	0.00
	50	.523	0.20
	55	.607	0.10
	60	.750	0.00
	64	.684	0.00
	76	.653	0.00
	80	.682	0.05
C-8-----	1	.485	0.00
	2	.705	0.00
	3	.687	0.00
	10	.727	0.00
	14	.463	0.10
	17	.741	0.00
	19	.628	0.00
	22	.787	0.00
	29	.575	0.00
	34	.500	0.10
	39	.673	0.00
	44	.673	0.05
C-9-----	49	.667	0.00
	53	.667	0.00
	57	.610	0.00
	58	.750	0.00
	67	.750	0.00
	1	.482	0.1
	3	.692	0.0
	6	.585	0.2
	8	.414	0.22
	12	.631	0.0
	17	.714	0.0
	21	.547	0.0
	27	.628	0.0




(Face p. 14) No. 16

8+000 7+000 6+000 5+000 4+000 3+000

TABLE OF WEIGHTS

SATURATION LINE	105 LB/CU.FT
(BUOYED)	60 LB/CU.FT
(D)	65 LB/CU.FT
(ED)	78 LB/CU.FT



2+00U

1+00U

AXIS

1+00D

2+00D

VALUES  
REQUIRED  
PRIOR TO  
OF L.O.

FOU

0.40

2250

0.30

2200

0.20

2150

0.10

2100

0.0

2050

2000

1950

0.1

NOTE:  
VALUES  
FROM  
SAMPLE  
O.W.  
X.S.  
O.E.

ON 3.4

SLIDE SURFACE

CORE LIMITS

REQUIRED

TAN #

TAN # IN CORE

NOTE: THIS SECTION WAS TAKEN NORMAL  
TO THE AXIS THROUGH THE FLARE  
OF THE DAM AT THE RIGHT ABUTMENT.


Figure 12

STA 12+75

# STATIC SLIDE ANALYSIS

VALUES OF FRICTION & COHESION  
REQUIRED ALONG BASE OF DAM JUST  
PRIOR TO SLIDE FOR FACTOR OF SAFETY  
OF 1.0

## FOUNDATION ANALYSIS




NOTE:  
VALUES OF FRICTION AND COHESION DETERMINED  
FROM CONSOLIDATED SHEAR TESTS ON UNDISTURBED  
SAMPLES ARE INDICATED THUS:  
O WEATHERED SHALE INVOLVED IN SLIDE  
X SURFACE CLAY  
□ BENTONITE □ BENTONITE QUICK SHEAR

## FORT PECK DAM STABILITY ANALYSIS

UPSTREAM SLOPE AT STA. 12+75

PRIOR TO SLIDE  
COMPILED BY D.H.M.  
2-4-39



9+00:0

8+00:0

7+00:0

6+00:0


5+00:0

4+00:0

3

# TABLE OF WEIGHTS

SAND MATERIAL ABOVE SATURATION LINE	105 LB/CU FT
" " BELOW (BOUYED)	80 " "
CORE MATERIAL (BOUYED)	65 " "
DISTURBED SHALE (BOUYED)	78 " "





3+00-U

2+00-U

1+00-U

AXIS

1+00-D

2+00-D

2401 BERM


LOW 3A


CORE LIMITS

SATURATION LINE


SLIDE SURFACE

TOP OF SUB-FIRM SHALE










STA 15+00






(Face p. 14) No. 19

1994

AL ABOVE SATURATION LINE	105 LB./CU.FT.
BELOW (BUOYED)	60 "
IT (BUOYED)	65 "
ALE (BUOYED)	78 "



2



3000 FT

2500 FT

2000 FT

AXIS

1500 FT

1000 FT

2300

2250

2200

2150

2100

2050

2000

2212 BERM

1000

SATURATION LINE

CORE LIMITS

SLIDE SURFACE


W. GROUND

FORT PECK DAM

3



Figure 15



10+00 U

9+00 U

8+00 U

7+00 U

6+00 U

5+00 U

## TABLE OF WEIGHTS

SAND MATERIAL ABOVE SATURATION LINE	105 LB./CU. FT.
BELOW (BUOYED)	60
CORE MATERIAL (BUOYED)	85
DISTURBED SHALE (BUOYED)	78

## VALUES OF FRICTION AND COHESION

MATERIAL	TAN $\phi$	COHESION, TONS/ SQ. FT.
SHELL	0.6	0
CORE	0.3	0
FOUNDATION	0.85	0.20

2300

2250

2200

2150

2100

2050

2000




Figure 17







Figure 18





15+00-U

14+00-U

13+00-U

12+00-U

11+00-U

10+00-U


9+00-U

TABLE OF WEIGHTS

SAND MATERIAL ABOVE SATURATION LINE 105 LB./CU.FT.  
 " " BELOW " " (BUOYED) 60 " "  
 CORE MATERIAL (BUOYED) 65 " "  
 DISTURBED SHALE (BUOYED) 78 " "


## VALUES OF FRICTION AND COHESION

MATERIAL	TAN $\phi$	COHESION TONS/SQ.FT.
SHELL	0.60	0.0
SLIDE	0.45	0.0
CORE	0.30	0.0
FOUNDATION	0.185	0.20



9+00-U      8+00-U      7+00-U      6+00-U      5+00-U      4+00-U      3+00-U

NOTE:  
SATURATION LINE AS SHOWN FOR  
FOR EXTREME CONDITIONS WHICH  
BE DEVELOPED ONLY BY Raising  
OF DAM BY HYDRAULIC FILL METHOD





00-U      2+00-U      1+00-U      AXIS      1+00-D      2+00-D      3+00-D

OWN PROVIDES  
S WHICH WOULD  
DURING CREST  
METHOD




Figure 19

2+00-D

3+00-D

4+00-D

STA. 12+75  
RECONSTRUCTION

## STATIC SLIDE ANALYSIS

2350

2300

2250

2200

2150

2100

2050

2000

1950

TAN  $\phi$ 

0.4

0.3

0.2

0.1

FOUNDATION ANALYSIS  
VALUES OF COHESION AND FRICTION  
FOR SOIL ALONG BASE OF DAMVALUE USED IN  
STABILITY ANALYSISREQUIRED  
FIELD SHEARING STRENGTHVALUE USED IN  
STABILITY ANALYSISPRIOR TO SLIDE (TAN  $\phi$  0.3 IN CORE)

COHESION

## NOTE:

VALUES OF FRICTION AND COHESION DETERMINED  
FROM CONSOLIDATED SHEAR TESTS ON TUBES

TURBED SAMPLES ARE INDICATED THUS:

O WEATHERED SHALE INVOLVED IN SLIDE

X SURFACE CLAY

□ BENTONITE □ BENTONITE QUICK SHEAR

## FORT PECK DAM

RECONSTRUCTION PLAN

STABILITY ANALYSIS OF PROPOSED BERM


UPSTREAM SLOPE AT STA. 12+75


COMPILED BY P.T.B.

2-8-58

5












Figure 20







16+00

15+00 U

14+00

13+00

12+00


11+00

10+00 U

SAND

CORE

DIST




10+00 U      9+00      8+00      7+00      6+00      5+00 U      4+00


TABLE OF WEIGHTS

SAND MATERIAL ABOVE SATURATION LINE	105 LB/CU FT.
BELOW (BUOYED)	80 "
CORE MATERIAL (BUOYED)	65 "
DISTURBED MATERIAL (BUOYED)	75 "

VALUES OF FRICTION AND COHESION

MATERIAL	TAN $\phi$	COHESION (TONS/30 FT.)
SHELL	0.60	0
SLIDE	0.45	0
CORE	0.30	0
FOUNDATION	0.185	0.20







FORT PECK

4

Figure 21



5



16+00-U

15+00-U

14+00-U

13+00-U

12+00-U


11+00-U


10+00

## TABLE OF WEIGHTS

SAND MATERIAL ABOVE SATURATION LINE  
 BELOW (BUOY)  
 CORE MATERIAL (BUOYED)  
 DISTURBED SHALE (BUOYED)

VALUES OF FRICTION AND COHESION  
 MATERIAL TANG COHESION, TONS/50  
 SHELL 0.30 0.0  
 SLIDE 0.45 0.0  
 CORE 0.30 0.0  
 CLAY SOILS 0.20 0.20  
 FOUNDATION 0.15 0.20





3

4+00-U

3+00-U

2+00-U

1+00-U

AXIS

1+00-D

2+00-D

EL. 2275.3

AM

IONA

2212 BERM

SATURATION LINE

PRESENT RING DAM

CORE LIMITS

0








Figure 22



5'



(Page 16) No. 7

12+000

11+000

10+000

9+000

8+000


7+000

## TABLE OF WEIGHTS

SAND MATERIAL ABOVE SATURATION LINE	63 LB./CU. FT.
BELOW (SLOPED)	60 " " " "
CORE MATERIAL (SLOPED)	65 " " " "

## VALUES OF FRICTION AND COHESION

MATERIAL	TAN $\phi$	COHESION
SHELL	0.40	0.0
CORE	0.30	0.0
FOUNDATION	0.20	0.25



6000

5000

4000

3000

2000

1000

PROPOSED CREST

104.33

2212.5874

104.13

2142.5874

104.33


SATURATION LINE

TOP W. 58

TOP 1. 58

TOP F. 58


3



FORT PECK DAM AND RESERVOIR EIBA

4

Figure 23








6000-U      10000-U      20000-U      30000-U      40000-U      50000-U      60000-U      70000-U      80000-U

TABLE OF WEIGHTS

WATER SATURATION LINE	105 (B/CU FT)
ADJ	(ADJUSTED) 60 " " "
ADJ	65 " " "
ADJ	70 " " "

TABLE OF FRICTION AND COHESION

TAN $\phi$	COHESION
0.50	0.0
0.30	0.0
0.20	0.20










Figure 24




4



FIGURE 26




WAR DEPARTMENT



**FORT W**

FIGURE 27



FORT PECK DAM AND RESERVOIR

ERODIMENT CRITERIA AND PERFORMANCE REPORT

PLATE 5-45








FIGURE 25



# MISSOURI RIVER IMPROVEMENT FORT PECK DAM

REVISED CROSS SECTIONS

SCALE 1"=100'

U.S. ENGINEER OFFICE, FORT PECK, MONTANA

MARCH 2, 1939

Drawn by T.A.	Traced by E.A.H.	Checked by J.W.	Sanctioned and letter J.W.	File No. 32-24
------------------	---------------------	--------------------	-------------------------------	-------------------

FORT PECK DAM AND RESERVOIR

ENGINEERING CRITERIA AND PERFORMANCE REPORT

PLATE 5-46

G.P.O.—160810



WAR DEPARTMENT

STA. 75+00

STA. 80+00

STA. 85+00

STA. 90+00

STA. 95+00

STA. 98+00

STA. 100+00

AXIS

2270  
2260  
2250  
2240  
2230  
2220

2210  
2200  
2190  
2180  
2170

2160

2150

2140 R. 10+00.11

2130

2120

2110

2100

2090

2080

2070 R. 15+00.11

2060

100'

AV. SLOPE 1 ON 33

SLOPE 1 ON 34

SLOPE 1 ON 50

SLOPE 1 ON 7

CREST EL. 2275.5

2160

2170

2180

2190

2200

2210

R. 8+00.11

R. 10+00.11

R. 15+00.11

FORT PEG

FIGURE 28

STA. 75+00

STA. 80+00

STA. 85+00

STA. 90+00

STA. 95+00

STA. 100+00

MISSOURI RIVER IMPROVEMENT  
**FORT PECK DAM**  
 PLAN OF LEFT ABUTMENT  
 UPSTREAM

SCALE 1"=100'


U.S. ENGINEER OFFICE, FORT PECK, MONTANA, MARCH 2, 1938

By	Checked by	Approved by	Scale
<i>W. J. ...</i>	<i>R. ...</i>	<i>...</i>	1/2" = 1'
1/25	1/25	1/25	1/25

FORT PECK DAM AND REMEDIATION


EMBANKMENT CRITERIA AND PERFORMANCE REPORT

PLATE 5-47



STA. 75+00 **FIGURE 28**

R 5+000



# MISSOURI RIVER IMPROVEMENT FORT PECK DAM

PLAN OF LEFT ABUTMENT  
DOWNSTREAM

SCALE: 1"=100'

U.S. ENGINEER OFFICE, FORT PECK, MONTANA.

MARCH 2, 1939.

Drawn by	Checked by	Approved by	Transmitted with letter dated	File No.
W.A.W.	W.A.W.	W.A.W.	3-2-39	32-33

MISSOURI RIVER IMPROVEMENT CRITERIA AND PERFORMANCE REPORT **PLATE 5-48**

S.P.O.—180810

LMED  
-83